

# 3D PRINTED BIU SATELLITE ANTENNA

---

Presentation Date |

November 2<sup>nd</sup>, 2022

RESTRICTION ON USE, PUBLICATION DISCLOSURE OF PROPRIETARY INFORMATION AND IMAGES

This document contains information proprietary to MacDonald, Dettwiler and Associates Corporation (MDA) to its subsidiaries, affiliates or to a third party to whom MDA may have a legal obligation to protect such information from unauthorized transfer, export, use, reproduction, or duplication. Any disclosure, transfer, export, use, reproduction, or duplication of this document, or of any of the information or images herein, other than for the specific purpose for which it was disclosed is expressly prohibited, except as MDA expressly agrees to in writing.

COPYRIGHT © 2022 MacDonald, Dettwiler and Associates Corporation (MDA), subject to General Acknowledgements for the third parties whose images have been used in permissible forms. All rights reserved.






# TABLE OF CONTENTS

1. INTRODUCTION
2. REQUIREMENTS
3. DESIGN
4. BUILD
5. TEST
6. LAUNCH
7. CONCLUSION
8. FUTURE


# 1. Introduction

- A few decades ago at MDA (formerly SPAR), a simple space satellite antenna would take about **2 years** to design, build, and test
- Leveraging the maturity of additive manufacturing (AM), we have delivered a flight antenna within **2 months**
- This presentation, tells the story of how this is possible



Then

Now



## 2. Requirements

- In the Summer of 2020, MDA was approached by one of its customers to provide 2 antennas for a January 2021 launch of a Bring-into-Use (BIU) Satellite
- We negotiated a simple antenna configuration consisting of a Transmit and Receive feed as well as a reflector and support structure
- RF, thermal, structural, programmatic, verification and documentation
  - Needed to transmit and receive suitably at the specified Ku and Ka frequencies to a target region from the specified orbit
  - Spacecraft was aluminum and the antenna was all-aluminum so no CTE mismatch or thermal concerns
  - Structural design environments were reasonable
  - One design review
  - Verification kept to a minimum
  - Bare bones documentation

### 3D PRINTED BIU SATELLITE ANTENNA

Disclosure, transfer, export, reproduction, duplication or publication of this document or any of the information or images contained herein is subject to the restrictions on the title page of this document.





### 3. Design

- To reduce assembly time each antenna was consolidated into three AISi10Mg parts bolted together.
- Parts were designed to minimize the need for AM printing supports, while still achieving optimal RF, structural, and mass performance (**2 weeks**)
  - Feeds designed so they could be printed with few supports
  - As-printed surface roughness of RF active surfaces taken into consideration to maximize RF performance
  - To minimize mass and provide optimal stiffness, support structure was designed using good “organic” engineering principles based on topological optimization of heritage structures
  - Parts were heat treated without sacrificing dimensional stability
  - Minimized post-machined surfaces (highlighted in **green**)
  - Minimized bolted interfaces (qty=8) to reduce assembly time


#### 3D PRINTED BIU SATELLITE ANTENNA

Disclosure, transfer, export, reproduction, duplication or publication of this document or any of the information or images contained herein is subject to the restrictions on the title page of this document.



## 4. Build

- 3D printing performed on two printers (Trumpf 2000 and EOS M400-4) using qualified processes
  - Reflector back-surface printing-supports designed to provide a compliant RF surface profile, yet be easily removed
- Precision post-machining only performed at interfaces
- Grit blast and chemical rinse performed to ensure cleanliness of bare surfaces




## 4. Build (continued)

- Burloak Technologies Incorporated (BTI), our AM partner, is a fully space-qualified 3D-printing production facility and NADCAP certified
  - Documented processes, paperwork, traceability, and all other standard QA and PA provisions
  - Successfully audited by MDA and MDA primes
- All aspects needed to produce and validate 3D printed parts are under one roof – this provides schedule, cost, quality, logistics and risk management – very efficient
  - Vertically integrated value stream - Printers, heat treatment furnaces, machining, inspection, grit blasting and cleaning, as well as material testing
- Requirements on Burloak are controlled via the drawing, purchase order, and the Source Control Document (SCD – i.e. specification), reflected in Burloak's standard operating procedures and specific program travelers


### 3D PRINTED BIU SATELLITE ANTENNA

Disclosure, transfer, export, reproduction, duplication or publication of this document or any of the information or images contained herein is subject to the restrictions on the title page of this document.



## 4. Build (continued)


- Inspection, validation, and Work in Process (WIP) tests performed at Burloak were reduced to the bare minimum
  - Powder chemical composition, size, tap and apparent density
  - Heat treat Certificate of Conformance (CofC)
  - Dimensional inspection report
  - Surface roughness measurement
  - Chemical composition (post heat treatment campaign)
  - Tensile yield, ultimate, and elongation (post heat treatment campaign)
- Results were provided in an End Item Data Package (EIDP)





## 4. Build (continued)

- Burloak delivered the 3D printed antenna parts **within 1 month**
  - AM AISi10Mg flight parts on Trumpf 2000 (Feeds) and M400-4 (Reflector and Support Structure)



### 3D PRINTED BIU SATELLITE ANTENNA

Disclosure, transfer, export, reproduction, duplication or publication of this document or any of the information or images contained herein is subject to the restrictions on the title page of this document.


## 4. Build (continued)

- The Ku/Ka Tx and Rx antennas, composed of only 3 parts, were bolted together with only 8 screws:
  - Feed/waveguide, structure and reflector



## 5. Test

- RF verification, structural vibration, packing, and delivery were performed in **2 weeks**, successfully meeting the 2 months schedule from contract award to delivery
- Both antennas were mounted in the compact antenna range test facility at MDA; S-parameters and RF pattern tests were performed – all compliant
- Afterwards, random vibration testing of both antennas was performed in all 3 axes successfully



## 6. Launch

- The antennas were assembled onto the spacecraft, the launch (Jan 20, 2021) was flawless
- The satellite is currently operational, with the antennas performing perfectly



## 7. Conclusion

- This presentation summarized the MDA BIU satellite antenna program that was successfully executed from contract award to delivery in 2 months, which was only possible by leveraging 3D printing and post processing services from our partners at Burloak






**Burloak  
Technologies**

a division of **SAMUEL** 1855

## 8. Future



- Presently, MDA uses this AM technology for numerous on-going space programs, including a follow-on BIU program currently underway.



# THANK YOU

---

